



NOTES:

1. NOTIFY Y.V.W.D. PRIOR TO INSTALLATION OF UNIT.
2. INSTALLATION SHALL COMPLY WITH THE LATEST PLUMBING CODES AND APPLICABLE LOCAL AGENCY REQUIREMENTS. DOUBLE CHECK ASSEMBLY MAY BE INSTALLED IN AN UNDERGROUND VAULT AS SHOWN IN YVWD STD. DWG. W-14.
3. ALL TEST VALVES MUST BE PLUGGED TO PREVENT TAMPERING.
4. MATERIALS 8 AND 9 ARE REQUIRED ON ALL ASSEMBLIES 6" AND LARGER. ASSEMBLIES SMALLER THAN 6" MAY REQUIRE A FULL LENGTH CONCRETE PAD BELOW THE DEVICE.
5. ALL BACKFLOW ASSEMBLIES ARE TO BE INSTALLED AS CLOSE AS POSSIBLE TO THE METER AND ON THE CUSTOMER SIDE OF RIGHT OF WAY.

LIST OF MATERIALS	
1	D.I.P. 90° ELBOW, MJ X MJ WITH MEGA LUGS
2	D.I.P. HALF SPOOL, FLG x PE
3	D.I.P. 90° ELBOW, FLG x FLG
4	WYE STRAINER
5	FULL SIZE BLOWOFF VALVE WITH PLUG TO PREVENT TAMPERING
6	APPROVED DOUBLE CHECK BACKFLOW ASSEMBLY
7	CHAIN AND LOCK BETWEEN VALVE HANDLES TO PREVENT TAMPERING
8	CONCRETE FOOTING
9	GALVANIZED ADJUSTABLE PIPE SUPPORT. SEE YVWD STD. DWG. W-25

DOUBLE CHECK BACKFLOW ASSEMBLY

2016



Yucaipa Valley Water District

Approved by the Yucaipa Valley Water District Board of Directors on March 16, 2016 as Resolution No. 2016-13

W-10