



NOTES:

1. NOTIFY Y.V.W.D. PRIOR TO INSTALLATION OF UNIT.
2. INSTALLATION SHALL COMPLY WITH THE LATEST PLUMBING CODES AND APPLICABLE LOCAL AGENCY REQUIREMENTS.
3. DOUBLE CHECK ASSEMBLIES MAY BE INSTALLED UNDERGROUND AS SHOWN IN STANDARD DRAWING W-14. RP ASSEMBLIES MAY NOT BE INSTALLED WITHIN A VAULT. ABOVE GROUND ONLY.
4. ALL TEST VALVES MUST BE PLUGGED TO PREVENT TAMPERING.
5. MATERIALS 8 AND 9 ARE REQUIRED ON ALL ASSEMBLIES 6" AND LARGER. ASSEMBLIES SMALLER THAN 6" MAY REQUIRE A FULL LENGTH CONCRETE PAD BELOW THE DEVICE.
6. ALL BACKFLOW ASSEMBLIES ARE TO BE INSTALLED AS CLOSE AS POSSIBLE TO THE METER AND ON THE CUSTOMER SIDE OF RIGHT OF WAY.
7. SEE SHEET 2 OF 2 FOR LIST OF MATERIALS.

DOUBLE CHECK OR REDUCED PRESSURE DETECTOR ASSEMBLY ABOVE GROUND FIRE LINE

2016



Yucaipa Valley Water District

Approved by the Yucaipa
Valley Water District Board of
Directors on March 16, 2016 as
Resolution No. 2016-13

W-13

Sheet 1 of 2

LIST OF MATERIALS

1	D.I.P. 90° ELBOW, MJ X MJ WITH MEGA LUGS
2	D.I.P. HALF SPOOL, FLG x PE
3	D.I.P. 90° ELBOW, FLG x FLG
4	WYE STRAINER
5	FULL SIZE BLOWOFF VALVE WITH PLUG TO PREVENT TAMPERING
6	APPROVED DOUBLE CHECK BACKFLOW ASSEMBLY
7	CHAIN AND LOCK BETWEEN VALVE HANDLES TO PREVENT TAMPERING
8	CONCRETE FOOTING
9	GALVANIZED ADJUSTABLE PIPE SUPPORT. SEE YVWD STD. DWG. W-25.
10	FACTORY INSTALLED BY-PASS METER ASSEMBLY CONSISTING OF APPROVED POSITIVE DISPLACEMENT METER, DOUBLE CHECK VALVE AND ASSOCIATED PIPING. BY-PASS METER TO BE SUPPLIED BY THE DISTRICT.

DOUBLE CHECK OR REDUCED PRESSURE DETECTOR ASSEMBLY ABOVE GROUND FIRE LINE

2016



Yucaipa Valley Water District

Approved by the Yucaipa
Valley Water District Board of
Directors on March 16, 2016 as
Resolution No. 2016-13

W-13